

4-22-04

9200/3743  
205,540

## IN THE UNITED STATES PATENT AND TRADEMARK OFFICE

Applicant: Krkobabic

Examiner:

A. Flynn

Application Number: 10/070,223

Group Art Unit:

3751

RECEIVED

Filing Date: June 21, 2002

APR 27 2004

Title: APPLICATORS AND APPLICATOR COMPONENTS TECHNOLOGY CENTER R3700

STATEMENT OF FILING BY EXPRESS MAIL 37 C.F.R. SECTION 1.10

This correspondence is being deposited with the United States Postal Service on April 20, 2004 in an envelope as "Express Mail Post Office to Addressee" Mail Label Number ET 537 590 159 US addressed to the Honorable Commissioner for Patents, Washington, D.C. 20231.

PETITION UNDER 37 C.F.R. § 1.181 TO  
WITHDRAW HOLDING OF ABANDONMENT

In response to the Notice of Abandonment dated November 19, 2003 in the above-captioned application, the applicant hereby petitions for the withdrawal of the holding of abandonment, due to the failure of the U.S. Patent and Trademark Office in receiving and/or properly processing a timely filed amendment dated and mailed July 7, 2003 (copy enclosed) in the present application, with such failure causing the improper abandonment of the present application.

## DISMISSAL OF THE PRESENT PETITION IS NOT WARRANTED

It is respectfully submitted that the present petition may be acted on and need not be dismissed, since the present application was in condition for allowance prior to the abandonment of the present application. Accordingly, since prosecution on the merits was closed, the examiner may consider the enclosed amendment purely for formal matters in furtherance of allowance and issuance of the present application.

## REMARKS

A non-final office action from the U.S. Patent and Trademark Office dated May 6, 2003, Paper Number 10, was received by the applicant. A time period of two months was specified in the non-final office action to file a response to address only formal matters, since the application was stated to be "in condition for allowance except for formal matters". Prosecution as to the merits was closed.

It is respectfully submitted that the applicant, through the undersigned, timely submitted a complete response to the non-final office action in the form of an amendment dated and mailed July 7, 2003 (July 6, 2003 being a Sunday, so such filing on July 7, 2003 was timely). A copy of the mailed amendment is submitted herewith.

As evidence of timely filing, it is noted that a certificate of mailing dated July 7, 2003 with express mail number ET537600046US was placed on the amendment as well as on all accompanying documents and a return receipt postcard. A copy of the unstamped return receipt postcard is enclosed.

A copy of the date-stamped U.S. Postal Service express mail label with express mail number ET537600046US dated July 7, 2003 is also enclosed, indicating that the applicant timely submitted the enclosed amendment by express mail with the U.S. Postal Service on July 7, 2003.

However, a Notice of Abandonment dated November 19, 2003 was entered and received by the applicant in the above-identified application. The U.S. Patent and Trademark Office held the application abandoned allegedly for the "Applicant's failure to timely file a proper reply to the Office letter mailed on 06 May 2003", that is, the aforesaid non-final office action dated May 6, 2003.

Since the failure of the U.S. Patent and Trademark Office to receive and/or properly process the timely filed amendment caused the present application to be improperly abandoned, the Commissioner is requested to grant the present petition, to withdraw the improper abandonment, and to enter the attached amendment.

It is respectfully submitted that dismissal of the present petition is not warranted, and that the present petition may be acted on, since the present application was in condition for allowance prior to the abandonment of the present application.

Accordingly, since prosecution on the merits was closed, consideration of only formal matters by the examiner is needed to allow and issue the application. Alternatively, it is respectfully submitted that the examiner may enter an examiner's amendment to address the formal matters and to further the present application to allowance and issuance.

Accordingly, entry and approval of the present petition, withdrawal of the abandonment of the present application, and allowance of all pending claims are respectfully requested.

Pursuant to M.P.E.P. § 711.03(c), page 700-154 (8th Ed., Rev. 1, Feb. 2003), no fee is required for the filing of the present petition. In case of any deficiencies in fees by submission of the present petition, the Commissioner is hereby authorized to charge such deficiencies in fees to Deposit Account Number 01-0035.

Respectfully submitted,



Anthony J. Natoli  
Registration number 36,223  
Attorney for applicant

Date: April 20, 2004

ABELMAN, FRAYNE & SCHWAB  
150 East 42<sup>nd</sup> Street  
New York, NY 10017-5612  
(212) 949-9022

## IN THE UNITED STATES PATENT AND TRADEMARK OFFICE

Applicant: Krkobabic Examiner: A. Flynn

Application Number: 10/070,223 Group Art Unit: 3751

Filing Date: June 21, 2002

Title: APPLICATORS AND APPLICATOR COMPONENTS

STATEMENT OF FILING BY EXPRESS MAIL 37 C.F.R. SECTION 1.10

This correspondence is being deposited with the United States Postal Service on July 7, 2003 in an envelope as "Express Mail Post Office to Addressee" Mail Label Number ET 537 600 046 US addressed to the Honorable Commissioner for Patents, Washington, D.C. 20231.

AMENDMENT

In response to the office action dated May 6, 2003 in the above-captioned application, please amend the above-captioned application as follows:

IN THE DRAWINGS:

Please replace sheets 1/13, 2/13, and 12/13 of the drawings, having FIGS. 1-3 and 15, with the attached replacement sheets 1/13, 2/13, and 12/13.

IN THE SPECIFICATION:

Please delete the entire specification and insert thereof the attached Substitute Specification (a marked-up copy of the amended pages of the original application as filed is attached, showing the amendments in red).

IN THE ABSTRACT:

Please delete the entire Abstract, and replace with the following new Abstract:

--ABSTRACT OF THE DISCLOSURE

A rotatable applicator head include a first part and a second part, with the first part being molded from a plastic material and being disk-like in form with a central recess formed in the first part. The second part is secured to the first part to form a liquid storage chamber between the first and second parts for storing a liquid to be applied to the surface of a field, garden or crop. A plurality of applicator wicks extend through a wall of the recess towards the periphery of the first part and having a portion with the recess. The wall is molded about the plurality of applicator wicks. A method forms a thermoplastic product with an exposed porous component, with a thermoplastic material injected about the compressed portion of porous material.--.

IN THE CLAIMS:

Please cancel claims 10-11, 14, and 19-22, without prejudice or disclaimer.

Please amend claims 1-9, 12-13, and 23 as follows:

1. (currently amended) A rotator applicator head including a first part and a second part, the first part being ~~moulded of a plastic~~ molded from a plastic material and being disk-like in form with a central recess formed therein, and said second part being secured to said first part capping said recess to define a liquid storage chamber between said first and second parts for storing a liquid to be applied to the surface of a field, garden or crop, and a plurality of applicator wicks extending through a wall of said recess towards the periphery of said first part and having a portion thereof within said recess, ~~characterized in that~~ wherein said wall is ~~moulded~~ molded about said plurality of applicator wicks.
2. (currently amended) A rotator applicator head according to Claim 1, wherein a portion of said first part at or near its periphery is ~~moulded~~ molded about a portion of each applicator wick to secure them against movement relative to said first part during rotation.
3. (currently amended) A rotator applicator head according to Claim 2, wherein intermediate portions of the first part are ~~moulded~~ molded about said wicks.



4. (currently amended) A rotator applicator head according to Claim 1, wherein each wick terminates adjacent the periphery of said first part and a peripheral portion of said first part is ~~moulded~~ molded about the end portion of each wick thereby forming a cap so that liquid flowing through the wick during rotation of the applicator head is prevented from flowing out the end of the wicks.
5. (currently amended) A rotator applicator head according to Claim 1, wherein said second part includes a Vee-belt pulley ~~integrally moulded therewith for receiving drive from a tractor power take-off (PTO) or other drive source.~~
6. (currently amended) An applicator, including:
- a frame assembly adapted to be attached to or drawn by a vehicle such as a tractor;
  - a support shaft secured to said frame assembly and depending therefrom in use;
  - ~~a storage tank mounted on said frame assembly or adapted to be mounted on the vehicle;~~
  - a rotatable applicator head as defined by Claim 1 mounted on said shaft for rotation relative thereto, said shaft extending into or through said storage chamber in said applicator head and said shaft having a passage therethrough, ~~said passage being in fluid communication with said storage chamber and said storage tank for supplying liquid to said storage chamber.~~

7. (currently amended) An applicator according to Claim 6, wherein ~~said~~ the shaft includes a second passage therethrough in fluid communication with ~~said~~ the storage chamber and adapted to act as a vent for venting ~~said~~ the storage chamber.

8. (currently amended) A hand held motor driven applicator including:  
 drive means having a drive housing and an output shaft, said drive housing being adapted to be coupled to an elongate handle by which a user may maintain said rotor applicator head proximal to the surface of a field, garden or crop, whereupon said applicator wicks may apply liquid to selected undesired plants upon contact therewith, and said drive means being adapted to be connected to a motor for driving said output shaft;

~~a motor drivingly connected to said drive means;~~

a rotatable applicator head connected to said output shaft for rotation therewith, said rotatable applicator head having a first part and a second part, said first part being ~~moulded~~ molded of a plastics material and being disk-like in form with a central recess formed therein, and said second part being secured to said first part capping said recess to define a liquid storage chamber between said first and second parts for storing a liquid to be applied to the surface of a the field, garden or crop, and a plurality of applicator wicks extending through a wall of said recess towards the periphery of said first part and having a portion thereof within said recess, said wall being ~~moulded~~ molded about said plurality of applicator wicks and ~~there being~~ including an access opening in said second part for receiving a supply of liquid ;

~~an elongate handle operatively connected to said drive housing by which a user may maintain said rotor applicator head proximal to the surface of the field, garden or crop, whereupon said applicator wicks may apply liquid to selected undesired plants upon contact therewith, and~~

~~a reservoir mounted on said elongate handle or said drive housing in fluid communication with said liquid storage chamber for supplying liquid to said liquid storage chamber via said access opening while said rotor applicator head is rotating.~~

9. (currently amended) A method of constructing a rotatable applicator head for a motor driven applicator of the type having a first part ~~moulded of a plasties~~ molded from a plastic material and being disk-like in form with a central recess formed therein and a plurality of applicator wicks extending through a wall of said recess towards the periphery of said first part and having a portion thereof within said recess, including :

cutting a piece of rope wick to a desired length to extend across a face of said first part;

compressing a portion of the rope wick and ~~moulding~~ molding said recess wall about said compressed portion of said rope wick while said rope wick is compressed, and

allowing the ~~plasties~~ plastic material to set; and

releasing the compression from said rope wick.

Claims 10-11 (canceled).

12. (currently amended) A method according to claim 9, wherein the characteristics of the materials and the parameters of the ~~moulding~~ molding process, particularly the temperature and injecting pressure, are selected such that some of the ~~thermoplastics~~ thermoplastic material penetrates part-way into the porous material in the ~~moulding~~ molding step.

13. (currently amended) A method according to claim 9, including the steps of cutting the rope with a hot blade to prevent fraying of the ends, and pressing the cut end into a V-shape.

Claims 14-22 (canceled).

23. (currently amended) A method according to claim 12, including the steps of cutting the rope with a hot blade to prevent fraying of the ends, and pressing the cut end into a V-shape.

REMARKS

Claims 1-9, 12-13, and 23 are amended; withdrawn claims 10-11, 14, and 19-22 are canceled, without prejudice or disclaimer; and claims 15-18 were previously cancelled. Claims 1-9, 12-13, and 23 are pending.

The amendments to the figures, specification, abstract, and claims are based on the application as originally filed, so it is respectfully submitted that no new matter has been added.

In the office action, the drawings were objected to, regarding features recited in claims 5-6 and 8. In addition, the drawings were objected to with regard to the reference numeral 11 for the "frame assembly 11".

Claims 5-6 and 8 have been amended to render the drawing objections moot. In addition, the recitation of the "Vee-belt pulley" of claim 5 is supported by pulley 41 shown in FIGS. 12a-12b; and the "drive means", "drive housing", and "output shaft" recited in claim 8 are supported by amended FIG. 15.

Sheets 1-2 and 12 of the drawings have been amended to include the reference numerals "11" in FIGS. 1 and 3; and reference numerals "115", "119", "120", "121", and "129" in FIG. 15.

Accordingly, reconsideration and withdrawal of the objections to the drawings are respectfully requested.

In the office action, the abstract and the specification were objected to based on the language thereof. The abstract and specification have been amended to overcome the objections.

In particular, the examiner objected to incorporation by reference to PCT/AU00/00167, and suggests amending the disclosure to include the incorporated material with an accompanying affidavit or declaration.

Instead, the applicant has deleted the incorporation-by-reference of the aforesaid PCT application, and includes, in the amended specification, a description of the features shown in FIG. 15, with reference to the added reference numerals "115", "119", "120", "121", and "129" in FIG. 15. It is respectfully submitted that the added description of the features in FIG. 15 are based on the present application as originally filed, including FIG. 15 and the other drawings of the present application, so no new matter has been added.

Accordingly, reconsideration and withdrawal of the objections to the abstract and specification are respectfully requested.

In the office action, it is stated that claims 1-9, 12-13, and 23 are objected to due to spelling errors, but will be allowed if the outstanding formal requirements are resolved.

The claims have been amended to correct any spelling errors, so claims 1-9, 12-13, and 23 are in condition for allowance. In addition, withdrawn claims 10-11, 14, and 19-22 were canceled.

Accordingly, entry and approval of the present amendment and allowance of all pending claims are respectfully requested.

In case of any deficiencies in fees by submission of the present amendment, the Commissioner is hereby authorized to charge such deficiencies in fees to Deposit Account Number 01-0035.

Respectfully submitted,



Anthony J. Natoli  
Registration number 36,223  
Attorney for applicant

Date: July 7, 2003

ABELMAN, FRAYNE & SCHWAB  
150 East 42<sup>nd</sup> Street  
New York, NY 10017-5612  
(212) 949-9022

1/13




FIG 2




FIG 1



2/13





FIG 3

12/13



**SUBSTITUTE SPECIFICATION****TITLE OF THE INVENTION****APPLICATORS AND APPLICATOR COMPONENTS****BACKGROUND OF THE INVENTION**5    **1. FIELD OF THE INVENTION**

**[0001]**       This invention relates to applicators for applying liquids to plants in a field, garden, crop or the like, particularly selective application of weedicides to undesired plants. The invention also relates to other applicator components including applicator heads and a method of constructing applicator heads particularly applicator heads constructed of a thermoplastics material having exposed porous components such as rope wicks for applying the liquid to the plants. The method of construction may have general application to the molding of other articles incorporating a thermoplastics material and a rope or other porous material.

15   **2. DESCRIPTION OF THE RELATED ART**

**[0002]**       Tractor mounted applicators for applying weedicides to crops etc are described in Australian patent No. 589361 and hand held applicators in our co-pending international applications No. PCT/AU00/00167 and No. PCT/AU98/00279. While such applicators are very effective in use, they are more expensive to manufacture and maintain than is desirable.

## SUBSTITUTE SPECIFICATION

## BRIEF SUMMARY OF THE INVENTION

[0003] With this in mind, the present invention is aimed at providing applicators and components for applicators which are less expensive to manufacture and result in apparatus which is more reliable and easier to maintain. The applicator discs illustrated  
5 in the aforementioned patent and applications have a central reservoir for storing liquid chemical and each wick passes through an aperture in the wall of the reservoir and is secured therein by a gland. The flow rate of liquid through the wick is dependent to some extent on the tightness of the gland and thus is sometimes difficult to control, or requires the use of extra devices associated either with the supply of liquid to the wick or wick  
10 itself. The present invention aims to provide a method of forming applicator discs which ameliorates one or more of the problems with the applicator discs presently used. Other aims and advantages of the invention may become apparent from the following description.

[0004] In one aspect, the present invention resides broadly in a rotatable  
15 applicator head including a first part and a second part, the first part being molded of a plastics material and being disk-like in form with a central recess formed therein, and said second part being secured to said first part to define a liquid storage chamber between said first and second parts for storing a liquid to be applied to the surface of a field, garden or crop, and a plurality of applicator wicks extending through a wall of said  
20 recess towards the periphery of said first part and having a portion thereof within said recess, characterized in that said wall is molded about said plurality of applicator wicks. Preferably, a portion of the first part at or near its periphery is molded about a portion of each applicator wick to secure them against movement relative to the first part during

## SUBSTITUTE SPECIFICATION

rotation. Intermediate portions of the first part may also be molded about the wicks for further security if desired. In a particularly preferred form in which each wick terminates adjacent the periphery of the first part, a peripheral portion of the first part is molded about the end portion of each wick thereby forming a cap so that liquid flowing through the wick during rotation of the applicator head is prevented from flowing out the end of the wicks. In a preferred form said second part includes a Vee-belt pulley integrally molded therewith for receiving drive from a tractor power-take-off (PTO) or other drive source.

[0005] Terms such as vertical, horizontal, upper and lower, are used herein for the purpose of description and illustration of the invention in the position it would normally be used for the application of weedicide to a field unless clearly not appropriate, and are not intended to restrict the scope of the invention to any particular orientation.

[0006] In another aspect the invention resides broadly in an applicator, comprising:

a frame assembly adapted to be attached to or drawn by a vehicle such as a tractor;

a support shaft secured to said frame assembly and depending vertically, in use, therefrom;

a storage tank mounted on said frame assembly or adapted to be mounted on the vehicle;

a rotatable applicator head as previously described mounted on said shaft for rotation relative thereto, said shaft extending into or through said storage chamber in said applicator head and said shaft having a passage therethrough, said passage being in fluid

## SUBSTITUTE SPECIFICATION

communication with said storage chamber and said storage tank for supplying liquid to said storage chamber. Preferably, said shaft also includes a second passage therethrough in fluid communication with said storage chamber and adapted to act as a vent passage for venting the storage chamber.

5 [0007] In another aspect, the invention resides broadly in a hand held motor driven applicator including:

drive means having a drive housing and an output shaft; a motor drivingly connected to said drive means;

a rotatable applicator head having a first part and a second part, the first part being  
10 molded of a plastics material and being disk-like in form with a central recess formed therein, and said second part being secured to said first part to define a liquid storage chamber between said first and second parts for storing a liquid to be applied to the surface of a field, garden or crop, and a plurality of applicator wicks extending through a wall of said recess towards the periphery of said first part and having a portion thereof  
15 within said recess, said wall being molded about said plurality of applicator wicks and there being an access opening in said second part for receiving a supply of liquid;

an elongate handle operatively connected to said drive housing by which a user may maintain said rotor assembly proximal to the surface of the field, garden or crop, whereupon said applicator wicks may apply liquid to selected undesired plants upon  
20 contact therewith, and

a reservoir mounted on said elongate handle or said drive housing in fluid communication with said liquid storage chamber for supplying liquid to said liquid storage chamber via said access opening while said rotatable applicator head is rotating.

## SUBSTITUTE SPECIFICATION

[0008] In another aspect, the invention resides broadly in a method of constructing a rotor head for a motor driven applicator of the type having a first part molded of a plastics material and being disk-like in form with a central recess formed therein and a plurality of applicator wicks extending through a wall of said recess towards the periphery of the first part and having a portion thereof within the recess including:

cutting a piece of rope wick to a desired length to extend across a face of the first part;

compressing a portion of the rope wick and molding the recess wall about the compressed portion of the rope wick while it is compressed, and

allowing the plastics material to set before releasing the rope wick. It will be appreciated that the method may be carried out for a plurality of rope wicks extending through the recess wall.

[0009] In yet another aspect, the invention resides broadly in a method of forming a thermoplastics product with an exposed porous component, including:

providing a component formed from a porous material;

supporting at least some of the porous material in a mold;

compressing a portion of the porous material supported in the mold;

injecting a thermoplastics material substantially about the compressed portion of the porous material; and

releasing the thermoplastics material and the porous material from the mold after the thermoplastics material has set.

## SUBSTITUTE SPECIFICATION

[0010] In another aspect, the invention resides broadly in a thermoplastics product with one or more exposed porous components manufactured in accordance with the method previously described.

[0011] Preferably, the compressing step is achieved by introducing a ram or  
5 pusher into the mold and engaging the ram with the portion of the porous material to be compressed prior to the introduction of the thermoplastics material, and injecting the thermoplastics material while the portion of porous material is compressed, and then removing the ram prior to the setting of the thermoplastics material, whereby the thermoplastics material back-fills the space previously taken up by the ram as it is  
10 withdrawn prior to solidification of the thermoplastics material.

[0012] Preferably, the characteristics of the materials and the parameters of the molding process, particularly the temperature and injecting pressure, are selected such that some of the thermoplastics material penetrates part-way into the porous material in the molding step. It will be appreciated that this will hold the rope more securely than if  
15 the plastics material simply abuts the surface of the rope and relies on the twist of the rope. In the case of the product being an applicator head and the porous material being rope wick, it is preferred that the thermoplastics material flow into the cavities and recesses between the external strands of the rope. It is believed that this will provide better control of flow so that all flow will be through the wick rather than around it.

20 [0013] Preferably, the method includes cutting the rope with a hot blade to prevent fraying of the ends, and also pressing the cut end into a V-shape. The rope is then preferably secured into a channel in the mold to prevent it sliding along the channel under the force of flow of the plastics material, with a length of rope passing out of the



## SUBSTITUTE SPECIFICATION

channel to provide a free end. In the case of an applicator head, the free end is destined to be located in the central recess for receiving liquid therefrom and a portion adjacent the free end (the restriction portion) is compressed and destined to have the wall of the central recess molded thereabout, while the portion adjacent the other end is compressed and destined to be completely encapsulated. In a preferred form the whole of the rope wick between the restriction portion and the other end is partially embedded in the thermoplastics material, the thermoplastics material extending part-circumferentially around the rope and along that length whereby the plastics material when set is keyed into the rope wicks to hold them securely against the disc-like first part of the applicator head. One or more supporting bands may be molded around that length also. The amount of compression of the restriction portion can be varied to provide a desired amount of throttling of the wick and the injecting pressure of the thermoplastics material can also be varied for this purpose. After the thermoplastics material has set to be sufficiently rigid, the mold is opened, the product ejected, and allowed to cool before further processing.

## BRIEF DESCRIPTION OF THE SEVERAL VIEWS OF THE DRAWINGS

[0014] In order that this invention may be more clearly understood and put into practical effect, reference will now be made to the accompanying drawings wherein:

Fig. 1 is a pictorial representation of a tractor mounted applicator according to the invention shown in the in-use attitude;

Fig. 2 is a front elevation of the applicator of Fig. 1 in the same attitude;

**SUBSTITUTE SPECIFICATION**

Fig. 3 is a pictorial representation of the applicator of Fig. 1 with some of the applicator units in an out-of-use attitude;

Fig. 4 is a bottom perspective view of a rotor head disk component of an applicator unit of the applicator of Fig. 1, with the rope wicks not shown for clarity;

5 Fig. 5 is a bottom plan view of the applicator disk of Fig. 4 also with the rope wicks not shown for clarity;

Fig. 6 is a top perspective view of the applicator disk of Fig. 4 also with the rope wicks not shown for clarity;

Fig. 7 is a side elevation of the applicator disk of Fig. 4 also with the rope wicks  
10 not shown for clarity;

Fig. 8 is a pictorial representation of a 1/12 segment of the disk of Fig. 4 with the rope wick incorporated;

Fig. 9 is a plan view of the segment of Fig. 8;

Fig. 10 is an elevation of the segment of Fig. 8;

15 Fig. 11a is a plan view of a cap for the recess of the applicator disc of Fig. 4;

Fig. 11b is a sectional elevation of the cap of Fig. 11a along line 11b-11b;

Fig. 12a is a plan view of a pulley adapted to be mounted to the cap of Fig. 11a;

Fig. 12b is a sectional elevation of the pulley of Fig. 12a along line 12b-12b;

Fig. 13a is an end view of a mounting shaft of an applicator unit of the applicator  
20 of Fig. 1, on which the rotor head is mounted;

Fig. 13b is a sectional view of the shaft of Fig. 13a along line 13b-13b; and

Fig. 14 is a pictorial representation of a mounting block by which the shaft of Fig. 13a is mounted to the frame assembly of the applicator of Fig. 1;

## SUBSTITUTE SPECIFICATION

Fig. 15 is a sectional elevation showing the main components of an applicator head for a hand held motor driven applicator according to the invention in the normal in-use orientation;

Fig. 16 is a plan view of a segment for a plastic rotor disc with a rope wick incorporated;

Fig. 17 is a sectional elevation along line 17-17 of the segment of the rotor disc of Fig. 16;

Fig. 18 is a diagrammatic sectional view showing the rope wick, die and plastic flow direction within the manufacturing die;

Fig. 19 is a diagrammatic sectional view of the rope wick of Fig. 18 showing a ram or pusher for compressing the rope in the manufacturing die;

Fig. 20 is a diagrammatic sectional view of the encapsulated end of the rope wick of the segment of Fig. 16.

## DETAILED DESCRIPTION OF THE INVENTION

[0015] The applicator 10 illustrated in Figs. 1, 2 and 3 includes a frame assembly 11 adapted to be mounted to the three point linkage of a tractor by a three point linkage mounting frame 12 and seven frame units 14 with three on each side of the center frame unit 14a which is mounted immediately behind the three point linkage mounting frame.

The outermost two units on each side of the center unit are welded together and are arranged for pivoting up and down movement together for travel as illustrated in Fig. 3 about pivot respective pivot pins 15.

## SUBSTITUTE SPECIFICATION

[0016] Seven applicator heads 13 depend from the respective frame units with each applicator head being rotatably mounted on a shaft 17 which in turn is clamped adjacent one end in a clamp block 18, as more clearly shown in Fig. 14. Each clamp block is welded to its respective frame unit and is of the split type which can be tightened onto the shaft by tightening two set bolts (not shown) which extend through the holes 19. This arrangement allows the shaft and the applicator head mounted thereon to be easily and quickly removed if desired.

[0017] Each applicator head 13 includes an applicator disk 21 as shown in Figs. 4, 5 and 6, but with the rope wicks incorporated as will be described later, and a top plate 22 as shown in Figs. 11a and 11b. A cup-like recess 23 is formed centrally of the applicator disk, the recess being defined by a substantially cylindrical side wall 24 and a base wall 26 with an aperture 27 being provided in the center of the base wall. The aperture is adapted to receive therein a bearing and seal by which the applicator head is mounted on the shaft 17 as will be described in more detail later. A shoulder 28 extends around the perimeter of the side wall as shown more clearly in Fig. 6 and the top plate 22 is seated on the shoulder and sonically welded to the side wall to form a storage chamber 29 defined by the base wall, the side wall and the top plate, for liquid chemicals such as weedicide. The disc has a thickened outer rim 30 at its periphery which provides strength and molding stability. The disk may be molded in one piece with the rope wicks extending radially from the central recess or in a plurality of pieces, for example twelve segments 21a as shown in Figs. 8, 9 and 10, which may be then welded together to form a disc.

## SUBSTITUTE SPECIFICATION

[0018] The discs 21 each have twelve equally spaced rope wicks 31 molded therein and extending into the recess 23 (which in part defines the liquid storage chamber 29) through passages 24a, as more clearly shown in the 1/12th segment of Figs. 8, 9 and 10, the ropes terminating in the outer rim in an end cap 32 and being held intermediate their two ends by two molded bands 33 and 34 as can be seen in Fig. 9. In the case shown, each segment is manufactured by an injection die molding process and the rope wicks are incorporated during the process, one to each segment. Each rope is first cut to length using a hot knife to prevent fraying. While the cut end is still molten, it is formed into a V-shaped tip to enable proper rope placement during the die closure. The first half of the manufacturing mold has a channel into which the desired length of rope wick is placed and the second half has two spaced apart locating pins 35 which are arranged to hold the rope in position when the mold is closed.

[0019] A mobile pusher platform is provided at 36 for positively locating the rope in the channel. This platform is withdrawn at a precise moment after the plastic has been introduced into the mold. Thermoplastics material is forced into the mold and forms a longitudinal cap on the rope wick in the channel, the completed segment having the appearance of the rope wick lying in a longitudinal recess 25 extending from the side wall 24 to the periphery of the disc. The second half of the mold has projections arranged so that the rope becomes supported on a plurality of bridging portions 25a so that the wicking properties are not significantly affected by being attached to the disc. The mold also has the necessary cavities and projections for forming a radially extending rib 39 flanking each rope wick to provide additional strength and fatigue resistance. In order to suitably secure the rope wick in the side wall 24, each rope wick is compressed at the

## SUBSTITUTE SPECIFICATION

position where the recess wall 24 is to be formed by a predetermined amount and the recess wall is then formed about the compressed portion of the rope. The amount of compression applied to the rope wick and the pressure at which the plastics material is injected mostly determine the cross sectional area of the rope wick over that portion

5 through the wall 24. Thus the wall acts to some extent like a gland and provides a means of restricting the flow rate of a particular chemical through the rope wick at a particular speed of rotation. A similar process is used to encapsulate the end portion of each rope wick in the end cap 32 shown in Fig. 8 to effectively close the end of each rope wick, the rope being pinched at 35 as shown in Fig. 17 and being allowed to stay at normal  
10 diameter within the end cap thereby being locked in as can be seen in Fig. 17. However, the supporting bands 33 and 34 (not shown in Figs. 16 and 17) are molded around the rope wick without any compression so that flow therethrough is not restricted.

[0020] Fig. 18 shows a portion of the die at 37 with the rope in position, and the flow of the plastic material is shown by respective arrows 38. In the process, as indicated  
15 in Figs. 19 and 20, the pusher 36 pushes the rope and deflects it to hold it in position. The pusher is pushed all the way into the die cavity, and the rope is placed manually into the channel of the first half of the mold. The V-tip end is placed 2 mm above the pusher. The die is then closed and the V-tip allows the end of the rope to slide into the channel on the other side of the die face which forms side wall 24. The plastic is injected and flows  
20 past the V-tip of the rope end. Because the V-tip is securely located at the bottom of the channel, the plastic does not dislodge the rope from the channel but compresses it along its length. If the rope end was not secure in the channel, it would be pushed along the channel and end up bunched up and deformed. Part way into the injection cycle, the

## SUBSTITUTE SPECIFICATION

pusher 36 is withdrawn and this allows plastic to backfill the exposed rope left by the withdrawal of the pusher. The die is cooled to cause the plastic to attain sufficient rigidity, then opened and the disc segment or complete disc as the case may be ejected and allowed to cool for at least 5 minutes before further work.

5 [0021] It will be appreciated from the foregoing description that a complete applicator head can be constructed in a very fast simple operation at very low cost with the rope wicks already mounted therein. It will also be appreciated that the applicator disk can be molded as one piece or as a plurality of segments for example, 1/12 segments which can be welded together to form a complete disk.

10 [0022] The pulley 41 illustrated in Figs. 12a and 12b is molded from a plastics material and is secured to the top cap 22 by four screws (not shown) which respectively pass through apertures 42a in the top plate and engage in the threaded bores 42a in the pulley. However, in another form of the invention, the pulley and the cap are molded as an integral unit.

15 [0023] As mentioned previously, the support shaft 17 is secured to the frame assembly by the clamp 18 and each applicator head is rotatably mounted on its respective shaft which in turn is mounted to its respective frame unit. As shown in Fig. 3, each shaft extends fully through its respective rotor head and is retained thereon by a washer and nut with a bottom seal and bearing being mounted in the applicator disk abutting a shoulder  
20 (not shown) in aperture 27 and a top seal and bearing mounted in the bore 43 of the pulley against shoulder 44. It will be seen from Fig. 13b that the top bearing engages the shaft portion 46 abutting shoulder 47 while the bottom bearing engages shaft portion 48 and the nut (not shown) is screwed to the shaft end portion 49.

## SUBSTITUTE SPECIFICATION

[0024] Two bores 51 and 52 extend through the shaft and open at the top 53 where standard hose fittings (not shown) are fitted, and at their other ends they open sideways through the shaft for fluid communication with the storage chamber 29. Both bores are connected by hoses (not shown) to a storage tank (not shown) mounted above the frame assembly 11, one hose being a supply hose connected to the lower part of the tank and connected to bore 52 while the other hose enters the tank above water level and is connected to bore 51 to act as a vent for the liquid storage chamber 29.

[0025] The applicator heads are driven by the tractor PTO via a right angle gearbox (not shown) mounted to bracket 20 with Vee-belts being drivingly connected to the output shaft of the gearbox and the center applicator head as well as the applicator heads on either side which in turn drive the next outer applicator heads and so on as can be seen in Fig. 2.

[0026] The hand held motor driven applicator 109 illustrated in Fig. 15 has an applicator head 113 which is constructed in a similar manner to that described in relation to the applicator 10, the wicks not being shown for clarity. The applicator 109 includes an angle drive gear box 115 having a drive housing 119 and an output shaft 120 to which the applicator head 113 is connected. An elongate handle (not shown) of the type typically used on brush cutters can be fitted to the socket 121 and a reservoir can be mounted on the handle and piped to the storage chamber 129.

[0027] Various modifications of the invention are contemplated which will be apparent to persons skilled in the art, and which can be resorted to without departing from the spirit and scope of the invention as defined in the appended claims.



**SUBSTITUTE SPECIFICATION**

**CLAIMS**

WHAT IS CLAIMED IS:

TITLE<sup>1</sup> OF THE INVENTIONAPPLICATORS AND APPLICATOR COMPONENTS~~BACKGROUND~~  
TECHNICAL FIELD OF THE INVENTION1. FIELD OF THE INVENTION

This invention relates to applicators for applying liquids to plants in a field, garden, crop or the like, particularly selective application of weedicides to undesired plants. The invention also relates to other applicator components including applicator heads and a method of constructing applicator heads particularly applicator heads constructed of a thermoplastics material having exposed porous components such as rope wicks for applying the liquid to the plants. The method of construction may have general application to the ~~moulding~~<sup>molding</sup> of other articles incorporating a thermoplastics material and a rope or other porous material.

2. DESCRIPTION OF THE RELATED ART  
BACKGROUND ARTBRIEF SUMMARY  
OF THE INVENTION

Tractor mounted applicators for applying weedicides to crops etc. are described in Australian patent No. 589361 and hand held applicators in our co-pending international applications No. PCT/AU00/00167 and No. PCT/AU98/00279. While such applicators are very effective in use, they are more expensive to manufacture and maintain than is desirable. With this in mind, the present invention is aimed at providing applicators and components for applicators which are less expensive to manufacture and result in apparatus which is more reliable and easier to maintain. The applicator discs illustrated in the aforementioned patent and applications have a central reservoir for storing liquid chemical and each wick passes through an aperture in the wall of the reservoir and is secured therein by a gland. The flow rate of liquid through the wick is dependent to some extent on the tightness of the gland and thus is sometimes difficult to control, or requires the use of extra devices associated either with the supply of liquid to the wick or wick itself. The present invention aims to provide a method of forming applicator discs which ameliorates one or more of the problems with the applicator discs presently used. Other aims and advantages of the invention may become apparent from the following description.

In one aspect, the present invention resides broadly in a rotatable applicator head including a first part and a second part, the first part being <sup>molded</sup> ~~moulded~~ of a plastics material and being disk-like in form with a central recess formed therein, and said second part being secured to said first part to define a liquid storage chamber between said first and second parts for storing a liquid to be applied to the surface of a field, garden or crop, and a plurality of applicator wicks extending through a wall of said recess towards the periphery of said first part and having a portion thereof within said recess, <sup>characterised</sup> ~~characterised~~ in that said wall is <sup>molded</sup> ~~moulded~~ about said plurality of applicator wicks. Preferably, <sup>molded</sup> ~~moulded~~ a portion of the first part at or near its periphery is <sup>molded</sup> ~~moulded~~ about a portion of each applicator wick to secure them against movement relative to the first part during rotation. Intermediate portions of the first part may also be <sup>molded</sup> ~~moulded~~ about the wicks for further security if desired. In a particularly preferred form in which each wick terminates adjacent the periphery of the first part, a peripheral portion of the first part is <sup>molded</sup> ~~moulded~~ about the end portion of each wick thereby forming a cap so that liquid flowing through the wick during rotation of the applicator head is prevented from flowing out the end of the wicks. In a preferred form said second part includes a Vee-belt pulley integrally <sup>molded</sup> ~~moulded~~ therewith for receiving drive from a tractor power-take-off (PTO) or other drive source.

Terms such as vertical, horizontal, upper and lower, are used herein for the purpose of description and illustration of the invention in the position it would normally be used for the application of weedicide to a field unless clearly not appropriate, and are not intended to restrict the scope of the invention to any particular orientation.

In another aspect the invention resides broadly in an applicator, comprising:

a frame assembly adapted to be attached to or drawn by a vehicle such as a tractor;

a support shaft secured to said frame assembly and depending vertically, in use, therefrom;

a storage tank mounted on said frame assembly or adapted to be mounted on the vehicle;

a rotatable applicator head as previously described mounted on said shaft for rotation relative thereto, said shaft extending into or through said storage chamber in said applicator head and said shaft having a passage therethrough, said passage being in fluid communication with said storage chamber and said storage tank for supplying liquid to said storage chamber. Preferably, said shaft also includes a second passage therethrough in fluid communication with said storage chamber and adapted to act as a vent passage for venting the storage chamber.

In another aspect, the invention resides broadly in a hand held motor driven applicator including:

drive means having a drive housing and an output shaft;

a motor drivingly connected to said drive means;

a rotatable applicator head having a first part and a second part, the first part being <sup>molded</sup> ~~molded~~ of a plastics material and being disk-like in form with a central recess formed therein, and said second part being secured to said first part to define a liquid storage chamber between said first and second parts for storing a liquid to be applied to the surface of a field, garden or crop, and a plurality of applicator wicks extending through a wall of said recess towards the periphery of said first part and having a portion thereof within said recess, said wall being <sup>molded</sup> ~~molded~~ about said plurality of applicator wicks and there being an access opening in said second part for receiving a supply of liquid;

an elongate handle operatively connected to said drive housing by which a user may maintain said rotor assembly proximal to the surface of the field, garden or crop, whereupon said applicator wicks may apply liquid to selected undesired plants upon contact therewith, and

a reservoir mounted on said elongate handle or said drive housing in fluid communication with said liquid storage chamber for supplying liquid to said liquid storage chamber via said access opening while said rotatable applicator head is rotating.

In another aspect, the invention resides broadly in a method of constructing a rotor head for a motor driven applicator of the type having a first part <sup>molded</sup> ~~moulded~~ of a plastics material and being disk-like in form with a central recess formed therein and a plurality of applicator wicks extending through a wall of said  
5 recess towards the periphery of the first part and having a portion thereof within the recess including:

cutting a piece of rope wick to a desired length to extend across a face of the first part;

compressing a portion of the rope wick and <sup>molding</sup> ~~moulding~~ the  
10 recess wall about the compressed portion of the rope wick while it is compressed, and

allowing the plastics material to set before releasing the rope wick. It will be appreciated that the method may be carried out for a plurality of rope wicks extending through the recess  
15 wall.

In yet another aspect, the invention resides broadly in a method of forming a thermoplastics product with an exposed porous component, including:

providing a component formed from a porous material; <sup>mold</sup>  
20 supporting at least some of the porous material in a ~~mould~~; <sup>mold</sup>  
compressing a portion of the porous material supported in the <sup>mold</sup> ~~mould~~;

injecting a thermoplastics material substantially about the compressed portion of the porous material; and  
25 releasing the thermoplastics material and the porous material from the <sup>mold</sup> ~~mould~~ after the thermoplastics material has set.

In another aspect, the invention resides broadly in a thermoplastics product with one or more exposed porous components  
30 manufactured in accordance with the method previously described.

Preferably, the compressing step is achieved by introducing a ram or pusher into the <sup>mold</sup> ~~mould~~ and engaging the ram with the portion of the porous material to be compressed prior to the introduction of the thermoplastics material, and injecting the  
35 thermoplastics material while the portion of porous material is compressed, and then removing the ram prior to the setting of the

thermoplastics material, whereby the thermoplastics material back-fills the space previously taken up by the ram as it is withdrawn prior to solidification of the thermoplastics material.

Preferably, the characteristics of the materials and the parameters of the <sup>moulding</sup> moulding process, particularly the temperature and injecting pressure, are selected such that some of the thermoplastics material penetrates part-way into the porous material in the <sup>moulding</sup> moulding step. It will be appreciated that this will hold the rope more securely than if the plastics material simply abuts the surface of the rope and relies on the twist of the rope. In the case of the product being an applicator head and the porous material being rope wick, it is preferred that the thermoplastics material flow into the cavities and recesses between the external strands of the rope. It is believed that this will provide better control of flow so that all flow will be through the wick rather than around it.

Preferably, the method includes cutting the rope with a hot blade to prevent fraying of the ends, and also pressing the cut end into a V-shape. The rope is then preferably secured into a channel in the <sup>mould</sup> mould to prevent it sliding along the channel under the force of flow of the plastics material, with a length of rope passing out of the channel to provide a free end. In the case of an applicator head, the free end is destined to be located in the central recess for receiving liquid therefrom and a portion adjacent the free end (the restriction portion) is compressed and destined to have the wall of the central recess <sup>moulded</sup> moulded thereabout, while the portion adjacent the other end is compressed and destined to be completely encapsulated. In a preferred form the whole of the rope wick between the restriction portion and the other end is partially embedded in the thermoplastics material, the thermoplastics material extending part-circumferentially around the rope and along that length whereby the plastics material when set is keyed into the rope wicks to hold them securely against the disc-like first part of the applicator head. One or more supporting bands may be <sup>moulded</sup> moulded around that length also. The amount of compression of the restriction portion can be varied to provide a desired amount of

throttling of the wick and the injecting pressure of the thermoplastics material can also be varied for this purpose. After the thermoplastics material has set to be sufficiently rigid, the <sup>mold</sup> ~~mould~~ is opened, the product ejected, and allowed to cool before further processing.

#### DETAILED DESCRIPTION OF THE DRAWINGS

In order that this invention may be more clearly understood and put into practical effect, reference will now be made to the accompanying drawings wherein:

Fig. 1 is a pictorial representation of a tractor mounted applicator according to the invention shown in the in-use attitude;

Fig. 2 is a front elevation of the applicator of Fig. 1 in the same attitude;

Fig. 3 is a pictorial representation of the applicator of Fig. 1 with some of the applicator units in an out-of-use attitude;

Fig. 4 is a bottom perspective view of a rotor head disk component of an applicator unit of the applicator of Fig. 1, with the rope wicks not shown for clarity;

Fig. 5 is a bottom plan view of the applicator disk of Fig. 4 also with the rope wicks not shown for clarity;

Fig. 6 is a top perspective view of the applicator disk of Fig. 4 also with the rope wicks not shown for clarity;

Fig. 7 is a side elevation of the applicator disk of Fig. 4 also with the rope wicks not shown for clarity;

Fig. 8 is a pictorial representation of a 1/12 segment of the disk of Fig. 4 with the rope wick incorporated;

Fig. 9 is a plan view of the segment of Fig. 8;

Fig. 10 is an elevation of the segment of Fig. 8;

Fig. 11a is a plan view of a cap for the recess of the applicator disc of Fig. 4;

Fig. 11b is a sectional elevation of the cap of Fig. 11a along line 11b-11b;

Fig. 12a is a plan view of a pulley adapted to be mounted to the cap of Fig. 11a;

Fig. 12b is a sectional elevation of the pulley of Fig. 12a along line 12b-12b;

Fig. 13a is an end view of a mounting shaft of an applicator unit of the applicator of Fig. 1, on which the rotor head is mounted;

5 Fig. 13b is a sectional view of the shaft of Fig. 13a along line 13b-13b; and

Fig. 14 is a pictorial representation of a mounting block by which the shaft of Fig. 13a is mounted to the frame assembly of the applicator of Fig. 1;

10 Fig. 15 is a sectional elevation showing the main components of an applicator head for a hand held motor driven applicator according to the invention in the normal in-use orientation;

15 Fig. 16 is a plan view of a segment for a plastic rotor disc with a rope wick incorporated;

Fig. 17 is a sectional elevation along line 17-17 of the segment of the rotor disc of Fig. 16;

20 Fig. 18 is a diagrammatic sectional view showing the rope wick, die and plastic flow direction within the manufacturing die;

Fig. 19 is a diagrammatic sectional view of the rope wick of Fig. 18 showing a ram or pusher for compressing the rope in the manufacturing die;

25 Fig. 20 is a diagrammatic sectional view of the encapsulated end of the rope wick of the segment of Fig. 16.

The applicator 10 illustrated in Figs. 1, 2 and 3 includes a frame assembly 11 adapted to be mounted to the three point linkage of a tractor by a three point linkage mounting frame 12 and seven frame units 14 with three on each side of the ~~center~~ <sup>center</sup> frame unit 14a which is mounted immediately behind the three point linkage mounting frame. The outermost two units on each side of the ~~center~~ <sup>center</sup> unit are welded together and are arranged for pivoting up and down movement together for travel as illustrated  
35 in Fig. 3 about pivot respective pivot pins 15.



Seven applicator heads 13 depend from the respective frame units with each applicator head being rotatably mounted on a shaft 17 which in turn is clamped adjacent one end in a clamp block 18, as more clearly shown in Fig. 14. Each clamp block is welded to its respective frame unit and is of the split type which can be tightened onto the shaft by tightening two set bolts (not shown) which extend through the holes 19. This arrangement allows the shaft and the applicator head mounted thereon to be easily and quickly removed if desired.

Each applicator head 13 includes an applicator disk 21 as shown in Figs. 4, 5 and 6, but with the rope wicks incorporated as will be described later, and a top plate 22 as shown in Figs. 11a and 11b. A cup-like recess 23 is formed centrally of the applicator disk, the recess being defined by a substantially cylindrical side wall 24 and a base wall 26 with an aperture 27 being provided in the <sup>center</sup> ~~centre~~ of the base wall. The aperture is adapted to receive therein a bearing and seal by which the applicator head is mounted on the shaft 17 as will be described in more detail later. A shoulder 28 extends around the perimeter of the side wall as shown more clearly in Fig. 6 and the top plate 22 is seated on the shoulder and sonically welded to the side wall to form a storage chamber 29 defined by the base wall, the side wall and the top plate, for liquid chemicals such as weedicide. The disc has a thickened outer rim 30 at its periphery which provides strength and <sup>molding</sup> ~~moulding~~ stability. The disk may be <sup>molded</sup> ~~moulded~~ in one piece with the rope wicks extending radially from the central recess or in a plurality of pieces, for example twelve segments 21a as shown in Figs. 8, 9 and 10, which may be then welded together to form a disc.

The discs 21 each have twelve equally spaced rope wicks 31 <sup>molded</sup> ~~moulded~~ therein and extending into the recess 23 (which in part defines the liquid storage chamber 29) through passages 24a, as more clearly shown in the 1/12th segment of Figs. 8, 9 and 10, the ropes terminating in the outer rim in an end cap 32 and being held intermediate their two ends by two <sup>molded</sup> ~~moulded~~ bands 33 and 34 as can be seen in Fig. 9. In the case shown, each segment is manufactured by an injection die <sup>molding</sup> ~~moulding~~ process and the rope wicks are

incorporated during the process, one to each segment. Each rope is first cut to length using a hot knife to prevent fraying. While the cut end is still molten, it is formed into a V-shaped tip to enable proper rope placement during the die closure. The first half of the manufacturing <sup>mold</sup> ~~mould~~ has a channel into which  
5 the desired length of rope wick is placed and the second half has two spaced apart locating pins 35 which are arranged to hold the rope in position when the <sup>mold</sup> ~~mould~~ is closed.

A mobile pusher platform is provided at 36 for positively locating the rope in the channel. This platform is withdrawn at  
10 a precise moment after the plastic has been introduced into the <sup>mold</sup> ~~mould~~. Thermoplastics material is forced into the <sup>mold</sup> ~~mould~~ and forms a longitudinal cap on the rope wick in the channel, the completed segment having the appearance of the rope wick lying in a longitudinal recess 25 extending from the side wall 24 to the  
15 periphery of the disc. The second half of the <sup>mold</sup> ~~mould~~ has projections arranged so that the rope becomes supported on a plurality of bridging portions 25a so that the wicking properties are not significantly affected by being attached to the disc. The <sup>mold</sup> ~~mould~~ also has the necessary cavities and projections for forming  
20 a radially extending rib 39 flanking each rope wick to provide additional strength and fatigue resistance. In order to suitably secure the rope wick in the side wall 24, each rope wick is compressed at the position where the recess wall 24 is to be formed by a predetermined amount and the recess wall is then  
25 formed about the compressed portion of the rope. The amount of compression applied to the rope wick and the pressure at which the plastics material is injected mostly determine the cross sectional area of the rope wick over that portion through the wall 24. Thus the wall acts to some extent like a gland and  
30 provides a means of restricting the flow rate of a particular chemical through the rope wick at a particular speed of rotation. A similar process is used to encapsulate the end portion of each rope wick in the end cap 32 shown in Fig. 8 to effectively close the end of each rope wick, the rope being pinched at 35 as shown  
35 in Fig. 17 and being allowed to stay at normal diameter within the end cap thereby being locked in as can be seen in Fig. 17.

However, the supporting bands 33 and 34 (not shown in Figs. 16 and 17) <sup>molded</sup> are moulded around the rope wick without any compression so that flow therethrough is not restricted.

Fig. 18 shows a portion of the die at 37 with the rope in position, and the flow of the plastic material is shown by respective arrows 38. In the process, as indicated in Figs. 19 and 20, the pusher 36 pushes the rope and deflects it to hold it in position. The pusher is pushed all the way into the die cavity, and the rope is placed manually into the channel of the first half of the <sup>mold</sup> mould. The V-tip end is placed 2 mm above the pusher. The die is then closed and the V-tip allows the end of the rope to slide into the channel on the other side of the die face which forms side wall 24. The plastic is injected and flows past the V-tip of the rope end. Because the V-tip is securely located at the bottom of the channel, the plastic does not dislodge the rope from the channel but compresses it along its length. If the rope end was not secure in the channel, it would be pushed along the channel and end up bunched up and deformed. Part way into the injection cycle, the pusher 36 is withdrawn and this allows plastic to backfill the exposed rope left by the withdrawal of the pusher. The die is cooled to cause the plastic to attain sufficient rigidity, then opened and the disc segment or complete disc as the case may be ejected and allowed to cool for at least 5 minutes before further work.

It will be appreciated from the foregoing description that a complete applicator head can be constructed in a very fast simple operation at very low cost with the rope wicks already mounted therein. It will also be appreciated that the applicator disk can be <sup>molded</sup> moulded as one piece or as a plurality of segments for example, 1/12 segments which can be welded together to form a complete disk.

The pulley 41 illustrated in Figs. 12a and 12b is <sup>molded</sup> moulded from a plastics material and is secured to the top cap 22 by four screws (not shown) which respectively pass through apertures 42a in the top plate and engage in the threaded bores 42a in the pulley. However, in another form of the invention, the pulley and the cap are <sup>molded</sup> moulded as an integral unit.

As mentioned previously, the support shaft 17 is secured to the frame assembly by the clamp 18 and each applicator head is rotatably mounted on its respective shaft which in turn is mounted to its respective frame unit. As shown in Fig. 3, each shaft extends fully through its respective rotor head and is retained thereon by a washer and nut with a bottom seal and bearing being mounted in the applicator disk abutting a shoulder (not shown) in aperture 27 and a top seal and bearing mounted in the bore 43 of the pulley against shoulder 44. It will be seen from Fig. 13b that the top bearing engages the shaft portion 46 abutting shoulder 47 while the bottom bearing engages shaft portion 48 and the nut (not shown) is screwed to the shaft end portion 49.

Two bores 51 and 52 extend through the shaft and open at the top 53 where standard hose fittings (not shown) are fitted, and at their other ends they open sideways through the shaft for fluid communication with the storage chamber 29. Both bores are connected by hoses (not shown) to a storage tank (not shown) mounted above the frame assembly 11, one hose being a supply hose connected to the lower part of the tank and connected to bore 52 while the other hose enters the tank above water level and is connected to bore 51 to act as a vent for the liquid storage chamber 29.

The applicator heads are driven by the tractor PTO via a right angle gearbox (not shown) mounted to bracket 20 with Vee-belts being drivingly connected to the output shaft of the gearbox and the <sup>center</sup> ~~center~~ applicator head as well as the applicator heads on either side which in turn drive the next outer applicator heads and so on as can be seen in Fig. 2..

The hand held motor driven applicator 109 illustrated in Fig. 15 has an applicator head 113 which is constructed in a similar manner to that described in relation to the applicator 10, the wicks not being shown for clarity. ~~The operation of the hand held applicator has been described in our co-pending international application No. PCT/AU00/00167 and the~~

~~specification relating to that application is incorporated herein~~  
The applicator 109 includes an angle drive gear box 115 having a drive housing 119 and an output shaft 120 to which the applicator head 113 is connected. An elongate handle (not shown) of the type typically used on brush cutters can be fitted to the socket 121 and a reservoir can be mounted on the handle and piped to the storage chamber 122.

~~by way of reference to the extent necessary for a complete understanding of the operation of that applicator.~~

Various modifications of the invention are contemplated which will be apparent to persons skilled in the art, and which can be resorted to without departing from the spirit and scope  
5 of the invention as defined in the appended claims.

What is Claimed is:

CLAIMS

1. A rotatable applicator head including a first part and a second part, the first part being moulded of a plastics material and being disk-like in form with a central recess formed therein, and said second part being secured to said first part to define  
5 a liquid storage chamber between said first and second parts for storing a liquid to be applied to the surface of a field, garden or crop, and a plurality of applicator wicks extending through a wall of said recess towards the periphery of said first part and having a portion thereof within said recess, characterised  
10 in that said wall is moulded about said plurality of applicator wicks.
2. A rotatable applicator head according to Claim 1, wherein a portion of said first part at or near its periphery is moulded  
15 about a portion of each applicator wick to secure them against movement relative to said first part during rotation.
3. A rotatable applicator head according to Claim 2, wherein intermediate portions of the first part are moulded about said  
20 wicks.
4. A rotatable applicator head according to Claim 1, wherein each wick terminates adjacent the periphery of said first part and a peripheral portion of said first part is moulded about the  
25 end portion of each wick thereby forming a cap so that liquid flowing through the wick during rotation of the applicator head is prevented from flowing out the end of the wicks.
5. A rotatable applicator head according to Claim 1, wherein  
30 said second part includes a Vee-belt pulley integrally moulded therewith for receiving drive from a tractor power-take-off (PTO) or other drive source.
6. An applicator, including:  
35 a frame assembly adapted to be attached to or drawn by a vehicle such as a tractor;

## IN THE UNITED STATES PATENT AND TRADEMARK OFFICE

Applicant: Krkobabic Examiner: A. Flynn

Application Number: 10/070,223 Group Art Unit: 3751

Filing Date: June 21, 2002

Title: APPLICATORS AND APPLICATOR COMPONENTS


STATEMENT OF FILING BY EXPRESS MAIL 37 C.F.R. SECTION 1.10

This correspondence is being deposited with the United States Postal Service on July 7, 2003 in an envelope as "Express Mail Post Office to Addressee" Mail Label Number ET 537 600 046 US addressed to the Honorable Commissioner for Patents, Washington, D.C. 20231.

ASSOCIATE POWER OF ATTORNEY

The undersigned attorney hereby appoints Anthony J. Natoli, Reg. No. 36,223; of ABELMAN, FRAYNE & SCHWAB, 150 East 42nd Street, New York, New York 10017, as associate attorneys in the above-identified application, to prosecute the aforesaid application and to transact all business in the United States Patent and Trademark Office in connection therewith.

Respectfully submitted,




Jay S. Cinamon  
Registration No. 24,156  
Attorney for Applicant

Date: July 7, 2003

ABELMAN, FRAYNE & SCHWAB  
150 East 42<sup>nd</sup> Street  
New York, NY 10017-5612  
(212) 949-9022




# POST OFFICE TO ADDRESSEE



<b>ORIGIN (POSTAL USE ONLY)</b>	
ZIP Code	Day of Delivery
7703	<input type="checkbox"/> Next <input type="checkbox"/> Second <input type="checkbox"/> Flat Rate Envelope
Mo. Day Year	<input type="checkbox"/> 12 Noon <input type="checkbox"/> 3 PM
AM PM	Military
1 PM	<input type="checkbox"/> 2nd Day <input type="checkbox"/> 3rd Day
Int'l Alpha Country Code	Postage \$
lbs. ozs.	Return Receipt Fee
Delivery	COD Fee Insurance Fee
Weekend <input type="checkbox"/> Holiday	Acceptance Clerk Initials
Total Postage & Fees \$	

SEE REVERSE SIDE FOR  
SERVICE GUARANTEE AND  
INSURANCE COVERAGE LIMITS



☐ **WAIVER OF SIGNATURE (Domestic Only)** Additional merchandise insurance is void if waiver of signature is requested. I wish delivery to be made without obtaining signature of addressee or addressee's agent (if delivery employee judges that article can be left in secure location) and I authorize that delivery employee's signature constitutes valid proof of delivery.

☐ **NO DELIVERY** ☐ Weekend ☐ Holiday

## CUSTOMER USE ONLY

**METHOD OF PAYMENT**  
Business Mail Corporate Acct. No. **X 093347**

**FROM: (PLEASE PRINT)**

PHONE ( )

Abelman, Prayne & Schwab  
150 East 42nd Street  
New York, NY 10017

Federal Agency Acct. No. or  
Postal Service Acct. No.

**TO: (PLEASE PRINT)**

PHONE ( )

COMMISSIONER FOR PATENTS  
P.O. Box 1450  
Alexandria, VA 22313-1450

ZIP + 4

						+				
--	--	--	--	--	--	---	--	--	--	--

FOR PICKUP OR TRACKING CALL 1-800-222-1811

www.usps.com



7-7-03



**Hon. Commissioner of Patents  
and Trademarks**

**Date Stamp as acknowledgement of receipt of:**

Applicant:	Krkobabic
Application Number:	10/070,223
Filing Date:	June 21, 2002
Group Art Unit:	3751
Examiner:	A. Flynn
Docket Number:	205,540
Certificate of Mailing Dated:	July 7, 2003

To the U.S. Patent and Trademark Office:

Please date stamp and return this postcard  
to acknowledge receipt of the following:


1. Amendment including:
  - a. Three (3) replacement sheets of drawings;
  - b. Substitute specification; and
  - c. Marked-up copy of original application
2. Associate Power of Attorney

Abelman, Frayne & Schwab

AJN

Mailed:  
Express Mail Number:

July 7, 2003  
ET 537 600 046 US



**ABELMAN FRAYNE & SCHWAB  
ATTORNEYS AT LAW  
150 EAST 42nd STREET  
NEW YORK, NY 10017**